3. The successful purchaser or lessee shall pay the balance of the lease amount within fifteen days after the confirmation of sale is intimated, failing which the amount deposited or the whole amount paid already as the case may be, will be forfeited to Government and the right resold subject to the conditions stipulated in para 2 *supra*.

4. The lessee shall sign an agreement binding himself to observe the following conditions, and it shall be executed within a week from the date on which the confirmation of the sale is intimated to him, in default of which, the money paid by him will be forfeited to Government and the right disposed of by resale at his risk as defined in paras 2 and 3 *supra*. The lessee shall not be allowed to enter the forest and cut bamboos until he has executed the agreement and further paid the balance of the lease amount.

Other conditions.

(*a*) The bamboos shall be collected or stored outside the block at such place or places as may be fixed by the Range Officer concerned and allowed to be removed on check by him and after a "permit to remove" is issued. Removal without such permits will be an offence to be dealt with according to law.

(*b*) The lessee shall not cut bamboos outside the limits of the block to which the lease refers.

(*c*) The lessee will be personally held responsible for the acts of his agents or servants or coolies in the business of collection and removal of bamboo and for preventing and cutting of clumps under two years by himself, his agents, servants or coolies.

(*d*) The lessee shall not sell the right purchased to other person or persons or appoint any agent or agents to work for him, without obtaining the previous permission in writing of the District Forest Officer.

(*e*) The lessee shall collect and remove the full quantity purchased from the limits of the Forest before the end of June 1924. No permission will be granted for cutting and collecting of bamboos after the 30th June 1924; but in very exceptional cases, an extension of time not exceeding three months will be granted by the District Forest Officer only for removal.

(*f*) The lessee shall accept the minimum quantity fixed in the notification as available in the block or area concerned and shall have no claim on the Department for any deficit that may be found. If he removes any quantity above the minimum fixed within the lease period, he will pay for the excess quantity at auction sale rates.

(*g*) The lessee shall abide by such orders as the District Forest Officer may issue regulating the transport of bamboos and collection at their rafting stations.

(*h*) The lessee will be held responsible for the occurrence of any fire within the forest if there is sufficient ground for the Forest Department to suspect that it was caused by his negligence or by that of his employees.

(*i*) Neither the lessee nor his employees shall enter the forest either before sunrise or after sunset.

5. No bamboos should be collected between 15th February and 30th April in the State Forests.

6. The sale does not prohibit the issue of retail licenses at seigniorage rates or the exercise of the rights of the villagers.

M. MACHAYA,
District Forest Officer.

ENGINEERING DEPARTMENT.

SANITARY DIVISION.

Dated 31st July 1923.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Sanitary Division, up to 10th September 1923, 12 A.M. for the Drainage work to the Town of Nelamangala. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed within six months after executing the bond which should be done immediately on the acceptance of tender.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified, will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred in cash or Government promissory notes, as earnest money, and be superscribed "Tender for the Drainage Work to the Town of Nelamangala" in default of which, tenders will be rejected.

5. It is not binding on the undersigned to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Drainage Scheme to the Town of Nelamangala.

Laying pipe sewers for diverting the sewage water of the Nelamangala Town beyond the Tank :—

PART A.

No.	Items of work	Per	Quantity
1	Cutting the bund and refilling for pipe sewer including watering and tamping	C. yds.	210
2	Removing and resetting old stone revetment	,,	65
3	Turfing the rear slops of bund cutting roots, etc.	S. yds.	400
4	Doulton's glazed stoneware pipes 9" diameter	R. ft.	300
5	Laying and jointing 9" S. W. pipes including carting	,,	300
	Constructing Manhole 4' x 4' x 4'.—		
1	Surki concrete	C ft.	35
2	Burnt brick in surki mortor	,,	104
3	Cement plastering	Sqrs.	0·80
4	Covering slabs 6" thick	S. ft.	36
5	Cutting grooves to slab for fitting the manhole cover	Each	1
6	C. I. Manhole cover and ring with casting, etc.	,,	1
	Cistern at the end of pipe sewer.—		
1	Surki concrete	C. ft.	30
2	Burnt brick in surki mortor	,,	69
3	3" burnt stone slab flooring with cement pointing	S. ft.	43
4	½" cement plastering (1 to 3)	Sqrs.	0·48
5	Chunam plastering	,,	0·56

Constructing intercepting Drains for the sewerage of Nelamangala Town :—

PART B.

No.	Items of work	Per	Quantity
1	Earthwork excavation in gravelly soil cutting and forming	C. yds.	660
2	Silk pattern concrete drains 4" (1)	R. ft.	250
	Do do 4" (2)	,,	1,220
	Do do 6" (6)	,,	200
	Do do 6" (7)	,,	780
3	Regrading the existing drains with old slabs, 5" (3)	,,	488
4	Do do 5" (4)	,,	136
5	Do do 4" (2)	,,	478
6	Do do 6" (7)	,,	850
7	New stone revetment	C. yds.	464
8	Burnt stone in chunam	C. ft.	1,800
9	5" to 6" burnt stone slab covering with pointing	S. ft.	640
10	Relaying existing drains	R. ft.	400

Detail statement showing the quantities of items required per R. ft. of silk pattern Drains for the Drainage Scheme of Nelamangala Town :—

No.	Items	Per	4" (1)	4" (2)	6" (6)	6" (7)	5" (3)	5" (4)	4" (2)	6" (7)
			Q	Q	Q	Q	With old slabs	With old slabs	With old slabs	With old slabs
							Q	Q	Q	Q
1	Surki concrete ..	C. yds.	·78	·78	·85	·95	·83	·94	·78	·95
2	Cement plastering ..	Sq. ft.	1·56	1·56	1·96	1·97	1·6	1·87	1·56	1·97
3	Removing and relaying of old slabs.	S. ft.	..	..	..	..	2·2	2·5	2	3·3
4	4" Burnt stone slabs ..	,,	1·5	2	2·6	3·3	..	..	..	..

H. F. MARKER.